BRUHAT BANGALORE MAHANAGARA PALIKE

SCHEDULE - B

Name of work: Estimate for Providing CC Road at A K Colony Singapura in Ward No. 11 (Kuvempunagara), Vidyaranyapura Sub Division.

Sl. No.	Approved Qty.	Description	Unit	Schedule-B Rates KRIDL		
				In Figures	Amount	In Words
1	84.00	KSRRB M200-12.2 : Dismantling of existing structures like culverts, bridges, retaining walls and other structure comprising of masonry, cement concrete, wood work, steel work, including T & P and scaffolding wherever necessary, sorting the dismantled materials, disposal of unserviceable material and stacking the serviceable material with all lifts and lead and lead of 10000 meters complete as per specifications. lime/cement concrete, I.by manual means B. cement concrete grade M-15 & M-20. **No. 136 / Item No. 18.18 / PWD SR 2015-16**	cum	375.24	31520.16	Rupees Three Hundred Seventy Five and Twenty Four Paise Only
2	125.99	KSRRB 300-1. Earth work excavation by manual means in ordinary soil involving an average horizontal throw upto 2 meters and an average lift upto 0.5m, excavated surface leveled and sides neatly dressed, the disposed earth to be leveled neatly after breaking of clods complete as per specifications complete as per specifications MORTH chapter 3. **Page No. 141 / Item No. 19.1 / PWD SR 2015-16**	cum	81.62	10283.30	Rupees Eighty One and Sixty Two Paise Only
3	577.80	Removing B.S Slab of Drain and stacking **Page No. 25 / Item No. 5.32 / PWD SR 2015-16**	Sqm	63.72	36817.42	Rupees Sixty Three and Seventy Two Paise Only
4	577.80	Refixing stone slabs of drains and pointing in C.M (1:3) **Page No. 25 / Item No. 5.33 / PWD SR 2015-16**	Sqm	78.84	45553.75	Rupees Seventy Eight and Eighty Four Paise Only
5	145.65	KSRB 4-1.3 : Providing and laying in position plain cement concrete of **mix 1:4:8 with OPC cement @ 180 kgs with 40mm** and down size graded granite metal coarse aggregates @ 0.85cum and fine aggregares @ 0.57 cum machine mixed, concrete laid in layers not, exceeding 15cms, thick, well compacted, in foundation and plinth, including cost of all materials, labour, HOM of machinery, curing complete as per specifications. Specification No. KBS 4.1,4.2. **No. 12/ Item No. 4.3/ PWD SR 2015-16**	Sqm	4976.70	724856.36	Rupees Four Thousand Nine Hundred Seventy Six and Seventy Paise Only
6	64.20	KSRB 4-6.4 : Providing and removing centering, shuttering, strutting, propping etc., and removal of form work for **vertical surface such as walls** at any thickness, including attached pilasters, buttresses, plinth and string courses cost of all materials, labour complete as per specifications. Specification NO KBS 4.6.2 **Page No. 15 / Item No. 4.31 / PWD SR 2015-16**	Sqm	306.72	19691.42	Rupees Three Hundred Six and Seventy Two Paise Only
7	121.38	Providing and laying cement concrete using 20mm and down size granite jelly of ready mixed concrete (RMC)for R.C.C works laid in 15cms thick layers and well compacted vibrating, curing, finishing with necessary cement mortar, form works and scaffoldings to withstand pumping of concrete, with all lead and lifts etc., complete (exclusive of cost of steel and fabrication charges.) Ready mixed Cement concrete M-20 (1:1.5:3) for raft foundation, column footing, main and secondary beams. **Page No. 18 / Item No. 4.48 / PWD SR 2015-16**	cum	6332.04	768583.02	Rupees Six Thousand Three Hundred Thirty Two and Four Paise Only
8	971.00	Vaccum De-watering with vaccum pump and suction mat and compaction with skin floater clubbed with floating disc including cost of generator HOM of machinery Screed Vibratiry, Power Floater, blade and disc etc., with all lead and lift No. **174 / Item No. 22.7 / PWD SR 2015-16**	Sqm	97.20	94381.20	Rupees Ninety Seven and Twenty Paise Only

EXECUTIVE ENGINEER-1
KRIDL, BBMP, DIVISION,
BANGALORE-560 010

Executive Engineer
Byatarayanapura Division
BBMP, Bangalore-92

27/8/16

Sl. No.	Approved Qty.	Description	Unit	Schedule-B Rates		
				KRIDL		
				In Figures	Amount	In Words
9	96.50	Providing **groove cutting** for width of 5mm to 10mm and depth 80mm-100mm including cost of cutting machine, generator and HOM of machinery including cost of blade coolant etc including cleaning of groove and providing sand and hot bitumne fillars, and filler metal etc., indluding cost of converyance of all materials, labours, lead and lift charges and all other incidental charges as per drawing and as per specification **Concrete Pavement Page No. 175 / Item No. 22.8.1 / PWD SR 2015-16**	Rmt	124.20	11985.30	Rupees One Hundred Twenty Four and Twenty Paise Only
10	94.49	Lead for Disposal of Debris shall be payable at carriage rates by Mechanical means inlcuding loading and unloading. From 0.00 to 2.00 Km (Page No.123)	cum	100.08	9456.56	Rupees One Hundred and Eight Paise Only
		Total			1753128.49	

Signature of the Contractor

EXECUTIVE ENGINEER-1
KRIDL, BBMP DIVISION
BANGALORE-560 010

Executive Engineer
Byarayanapura Division
BBMP, Bangalore - 92

5/8/14

05/08